

GORDON MARQUIS™ LINEAR WALL PANEL SYSTEMS

SECTION 09 78 13

PART 1 – GENERAL

1.01 SECTION INCLUDES:

- A. This section includes MARQUIS™ Metal Wall Panels as shown on the Architectural Drawings.
- B. Related sections include the following: (list applicable sections).

1.02 RELATED DOCUMENTS/SECTIONS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions.
- B. Division 1 Specification sections apply to work of this Section.
- C. Finish Schedule or Finish Legend applies to work of this Section.

1.03 REFERENCES:

- A. GENERAL
 - 1. Comply with applicable requirements of the following, except where more stringent requirements are indicated by building codes.
- B. ASTM (American Society for Testing and Materials)
 - 1. B209 Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
 - 2. E84 Standard Test Method for Surface Burning Characteristics of Building Materials
- C. The Aluminum Association Standards and Data

1.04 DESIGN/PERFORMANCE REQUIREMENTS:

- A. All components of the MARQUIS™ Metal Wall Panels System shall be provided by one (1) Manufacturer to ensure single source responsibility and quality control.

1.05 SUBMITTALS:

- A. Submission must be made within ten (10) working days of the General Contract Award to avoid project delay.
- B. Product Data: Submit Manufacturer's technical data and brochures of the specified system.
- C. Shop Drawings shall show dimensions, sizes, thickness, finishes, joining, mounting attachments, and relationship to adjoining work.
- D. Samples:
 - 1. Samples shall include a minimum 8" long nominal piece X the module width of each type of metal Panel, finished as specified, and accessories.
- E. Certification: Submit certification from Manufacturer of Wall Panels attesting that products comply with specified requirements including finish as specified.

- F. Qualification Data:
 - 1. Firms specified in "Quality Assurance" Article must demonstrate their capabilities and experience by including lists of completed projects with project names and addresses, names and addresses of Architects and owners, and other information specified.
- G. Product Test Reports:
 - 1. All products furnished shall have a flame spread classification of 0-25 for a Class A or Class 1 rating in accordance with ASTM E84.
 - 2. All products furnished shall be tested in accordance with ASTM C-423 for Sound Absorption.
- H. Maintenance Data:
 - 1. Provide maintenance instructions for acoustical Panels to be included in maintenance manuals as specified in Division 1.
- I. Warranty:
 - 1. Provide product warranty for one (1) year from date of material shipment.

1.06 QUALITY ASSURANCE:

- A. Manufacturer: Furnish components from one (1) Manufacturer with a minimum of ten (10) years of experience in the fabrication of metal wall specialties, utilizing systems, materials, and techniques as herein specified.
- B. Installer: Firm with not less than three (3) years of successful experience in the installation of systems similar to those required by this project and acceptable to Manufacturer of the system.
- C. Fabricator must own and operate its own manufacturing facilities for all metal components. Systems consisting of components from a variety of Manufacturers will not be considered or accepted.
- D. Manufacturer/Fabricator must own and operate its own Painting and Finishing facility to assure single source responsibility and quality control.
- E. Testing Agency Qualifications: An independent testing agency, acceptable to authorities having jurisdiction, with the experience and capability to conduct testing indicated, as documented according to ASTM E 548.

1.07 PRODUCT DELIVERY, STORAGE AND HANDLING:

- A. All materials shall be protected during fabrication, shipment, site storage, and erection to prevent damage from other trades. Store MARQUIS™ Wall Panels and components inside a well-ventilated area, away from uncured concrete and masonry, and protected from the weather, moisture, soiling, abrasion, extreme temperatures, and humidity.

1.08 SEQUENCING:

- A. Substitute Products: Alternate proposals for substitute products will not be accepted unless approval is issued in addenda.
- B. Contract Execution: Submittals shall be completed and approved prior to award of subcontract for system components.
- C. Manufacturer's Production Schedule: Sub-contract for the work of this section shall be planned to allow sufficient time for Manufacturer's production and delivery scheduling.

1.09 WARRANTY:

- A. Furnish Manufacturer's:
 - 1. Warranty that materials furnished will perform as specified for a period of not less than one (1) year from date of material shipment when installed in accordance with Manufacturer's recommendations.

PART 2 - PRODUCTS

2.01 MANUFACTURERS:

- A. Acceptable System: MARQUIS™ Metal Wall Panel Systems shall be manufactured by Gordon, Inc. For all inquiries contact, Gordon, Inc., 5023 Hazel Jones Road, Bossier City, LA 71111, (800) 747-8954.
- B. The listed Manufacturer shall not be construed as closing specifications to other prospective Manufacturers, but rather as establishing a level of quality in a metal system. Other systems may be submitted for approval, as provided for in the specifications at least ten (10) working days prior to submission of bids. Companies desiring to submit a proposal shall submit all descriptive information of the system proposed including photographs and Shop Drawings of at least three (3) projects similar in detail and scope.

2.02 PRODUCT CONSTRUCTION:

- A. Wall System shall be MARQUIS™ Linear Wall Panel Systems. All Panels, Perimeter Trims and fasteners, including acoustical component, shall be provided as a complete package of this work.
- B. Materials: Metal Panels:
 - 1. Aluminum sheet shall be 3003-H14 alloy, minimum 0.040" recommended per ASTM B 209.
 - 2. Panels are (4", 6", 8", or 12") module widths, non-perforated or perforated, and formed to a MARQUIS™ pattern.
 - a. Standard Perforation – Panels will be 1/16" diameter holes on 5/32" diagonal centers, approximately 12% open area and perforated on the face with a 3/8" non-perforated nominal border. Panels are 10' in length standard. OR
 - b. Custom Perforation -Please contact Gordon, Inc. for custom perforation patterns.
 - 3. The Panels shall be fabricated of smooth aluminum.
 - 4. Optional Sound Absorption Material:
 - a. For Interior use only, provide non-woven acoustical fabric to the back side of panels (NRC: 0.75). OR
 - b. For Interior or Exterior use, provide fiberglass (1" or 2" or other thickness) X (1.5 #, 2 #, or other density). The fiberglass Panel shall be wrapped in Class A, per ASTM E84 (Black Polyvinylchloride or Black Polyethylene). NRC Range: 0.80 to 1.0.

C. Accessories:

1. J trim, factory painted screws, and internal splices required for a complete system as necessary.
2. Furring channels/structural supports are to be provided by others.
3. General: Provide metals free from surface blemishes where exposed to view in finished unit. Surfaces that exhibit pitting, seam marks, roller marks, stains, and discolorations, or other imperfections on finished units are not acceptable. All metal shall be of the highest-grade commercial type.

2.03 FINISHES:

A. Finishes

1. MARQUIS™ Panels shall receive 5-stage pretreatment with dried-in-place conversion coating prior to receiving an electrostatically applied AAMA 2604 or AAMA 2605 compliant powder coating finish.
2. All cut edges, including perforated holes, must be coated. Finish shall oven baked to ensure complete curing, paint adhesion, and uniform surface hardness.
3. Paint color to be selected from Gordon, Inc.'s list of Standard colors (custom colors also available).

B. Panels may have a factory-applied wood-look finish:

1. Laminated Wood-Look Films – Series 1
2. Laminated Wood-Look Films – Series 2
3. Wood-Look Paints

2.04 FABRICATION:

- A. Height of Wall Panels shall be up to 12'-0" without horizontal joints.
- B. Wall Panels shall have either a closed or reveal vertical joint, as shown in the Architectural Drawings. All other details, including base and wall details, shall be fabricated in accordance with the Architectural Drawings.

PART 3 - EXECUTION

3.01 EXAMINATION:

- A. Examine building structure scheduled to receive Wall System for unevenness or irregularities that would affect quality and execution of work.
- B. Tolerances:
 1. Install Wall System with maximum permissible deflection of L/360 of span and maximum surface deviation of 1/8" in 4'-0" (No load applied).

3.02 PREPARATION:

- A. Clean surfaces thoroughly prior to installation.
- B. Prepare surfaces using the methods recommended by the Manufacturer to achieving the best result for the project conditions.

3.03 INSTALLATION:

- A. General: Comply with Manufacturer's printed instructions, and with any standards applicable to work.
- B. Space Enclosure: Do not install any work until space is enclosed and weatherproofed, wet-work in space is completed and nominally dry, work above ceilings is complete, and temperature and humidity shall be continuously maintained at values near those of final occupancy.

3.04 CLEANING:

- A. Follow Manufacturer's cleaning instructions for specified finish.

3.05 PROTECTION:

- A. Procedures: Protection of MARQUIS™ Wall Systems from damage by other trades after installation to be provided by General Contractor.
- B. Damage to Finished Work: Finished units shall be without damage. Damage shall be repaired by the Contractor at the expense of the party damaging the material, as in accordance with the contract requirements.

END OF SECTION